SIMULTANEOUS TUBULAR HANDLING SYSTEM

SPECIFICATION

CROSS-REFERENCE TO RELATED APPLICATIONS

[0001] N/A

STATEMENT REGARDING FEDERALLY SPONSORED RESEARCH OR DEVELOPMENT

[0002] N/A

REFERENCE TO MICROFICHE APPENDIX

[0003] N/A

BACKGROUND OF THE INVENTION

[0004] 1. Field of the Invention

[0005] This invention relates to a novel method and system for transporting, assembling, storing, and disassembling oilfield tubulars in and around a single drilling deck, derrick, and rotary system while drilling operations are simultaneously and independently occurring.

[0006] 2. Description of the Related Art

[0007] Drilling for oil and gas with a rotary drilling rig is being undertaken to increasingly greater depths both offshore and on land. The increase in depth translates into longer drilling time, and increased cost. The cost to operate such rigs is already substantial (rental rates for

some offshore rigs can exceed U.S. $400,000 to $500,000 per day). Therefore, any productive operation that can be accomplished independently of drilling operations to save even small amounts of time in the drilling process is economically significant.

[0008] The term "tubular" as used herein means all forms of drill pipe (including heavy weight drill pipe, such as HEVI-WATE™ tubulars), casing, drill collars, liner, bottom hole assemblies, and other types of tubulars known in the art. HEVI-WATE™ is a registered trade mark of Smith International, Inc. of Houston, Texas. Drilling operations require frequent stops when a small part of the tubular string extends above the drilling deck. Additional tubulars must be moved from a storage rack and connected with the upper end of the tubular string, which may cause significant delay in drilling. The length of a typical single drill pipe section is 30 feet (about 10 m). A stand is created by connecting together two or more single sections of tubulars. In the past, stands have been assembled or made up with four or five single sections of tubulars. A top drive rotary system is often used in place of the rotary table to turn the drill string, and is now the prevalent method of rotary drilling. One of the benefits of the top drive is that it can drill with pre-assembled tubular stands. Therefore, the creation and handling of tubular stands independently of the drilling process is a potentially important way to save time and money.

[0009] A method and system of handling tubulars simultaneously with drilling operations is described in U.S. Pat. No. 4,850,439 to Lund, the disclosure of which is incorporated herein by reference for all purposes. Lund proposes a preparation hole and an auxiliary hoist for offline stand building. While drilling operations are occurring, Lund proposes a first tubular being lifted in a vertical position when the auxiliary hoist is moved upward so that the tubular is swung from the cable over and then lowered into the preparation hole. Lund proposes that another tubular can then be swung over the first tubular for connection ('439 patent, col. 7, ln. 58 to col. 8, ln. 19). For a third tubular, if the free space below the top of the preparation hole is less than the length of two tubulars, Lund proposes another auxiliary hoist. In such circumstance, the preparation hole must be displaced or tilted from the vertical suspension line of the first auxiliary hoist ('439 patent, col. 9, ln. 58 to col. 10, ln. 46).

[0010] Another offline stand building method and system has been proposed by Smedvig Asia Ltd. of Singapore. Smedvig proposes a self erecting offshore tender rig to transfer and erect drilling equipment on a platform. After the drilling equipment is erected on the platform, Smedvig proposes a high line cable system to move tubulars from the tender rig to the platform, a racker crane at the top of the derrick that moves parallel to the drilling deck, and two preparation holes.

[0011] Smedvig proposes that while drilling operations are occurring on the platform, a single tubular on the rig can be manually connected at both ends while in horizontal position to the high line cable system. The high line cable system is used to lift and transport the tubular across the water from the rig to the pipe ramp on the platform, where the tubular is manually disconnected. A gripping device connected by cable to a hoist on the racker crane is then manually connected to the upper end of the tubular on the pipe ramp. The tubular is then hoisted in the vertical position, and swung from the cable over the first preparation hole. The tubular is then lowered into the hole, and the gripping device released. The process can be repeated with a second tubular, which can be swung into position in the second preparation hole. The process can be repeated with a third tubular for connection with the first tubular into a double stand. The double stand is then hoisted by the racker crane and lowered for connection with the second tubular for a triple. The completed stand is hoisted up and carried by the racker crane to a vertical tubular storage rack at the top of the derrick. Smedvig also proposes that the first preparation hole can have an adjustable bottom for acceptance of different size tubulars.

[0012] Another offline stand building method and system is proposed in U.S. Pat. No. 6,976,540 to Berry, the disclosure of which is incorporated herein by reference for all

purposes. Berry proposes, among other things, a load and preparation pipe handling device ("preparation device"), a storage pipe handling device ("storage device"), and tubular storage areas at the top of the derrick. The preparation device includes a vertical truss rotatable about its longitudinal axis. The preparation device includes a gripping device attached at the end of a hoisting cable extending out from the vertical truss. The gripping device is manually attached to one end of a tubular that has been placed near the preparation device on the catwalk or the pipe ramp so that when the cable is retracted back toward the preparation device, the lifted tubular is swung from the cable, similar to the Lund and Smedvig systems.

[0013] Berry then proposes that the truss can then swing the vertical tubular in a circular path to a first preparation hole, which has been placed along the path. The preparation device can then lower the first tubular into the first preparation hole. Using two preparation holes, much like the Smedvig system, a stand is assembled. The assembled stand is then lifted vertically by the preparation device to the top of the derrick, and directly exchanged to the storage device, which can either store it or transport it for drilling operations ('540 patent, col. 7, lns. 26-40 and col. 8, lns. 30-35).

[0014] The oil industry has proposed systems for the online transferring of tubulars from the horizontal position on a pipe rack to the vertical position over the well center. One such

system is proposed in U.S. Pat. No. 4,834,604 to Brittian et al., the disclosure of which is incorporated herein by reference for all purposes. Brittian proposes a strongback connected to a boom that is pivotally fixed to a base located adjacent to the rig. The strongback transfers the tubular directly through the V-door from a horizontal position to a vertical position so that a connection between the tubular and the tubular string can be made. Another system is proposed in U.S. Pat. No. 6,220,807 to Sorokan, the disclosure of which is incorporated herein by reference for all purposes. An online pipe handling system is proposed for using a bicep arm assembly pivotally connected to a drilling rig, and a forearm assembly and a gripper head assembly both pivotally connected to the bicep arm assembly. The gripper head assembly grabs the horizontal positioned tubular on the pipe rack adjacent to the rig, and rotates the tubular to a vertical position over the well center.

[0015] A horizontal to vertical pipe handling system is proposed in Pub. No. US 2006/0151215 to Skogerbo. Skogerbo discloses an Eagle Light/HTV-Arm, which is distributed by Aker Kvaerner MH of Houston, Texas. The Eagle Light HTV (horizontal to vertical) device is proposed for online transfer of tubulars from a horizontal position at the catwalk to a vertical position in the derrick directly over the well center or into the mousehole. Aker Kvaerner MH also distributes bridge crane systems and storage

fingerboards. National Oilwell Varco of Houston, Texas also manufactures a similar HTV online pipe handling device.

[0016] Another online method and apparatus for transferring tubulars between the horizontal position on the pipe rack to the vertical position over the well center is proposed in U.S. Pat. No. 6,705,414 to Simpson et al. Simpson proposes a bucking machine to build tubular stands in the horizontal position on the catwalk. A completed stand is horizontal at a trolley pick-up location, and becomes vertical at the rig floor entry. The stand, clamped to a trolley, is pulled along and up a track with a cable winch. A vertical pipe racking device located in the upper derrick is proposed to transfer the stand directly from the trolley.

[0017] The disadvantages of the above tubular handling methods and systems include significant human physical contact with the tubulars and lifting equipment at numerous times and locations, which can result in costly delay or possible injury. The alignment and transfer operations are lengthy and complex. The paths of the tubulars in the offline stand building are not fully restricted, which creates delay and safety hazards. The offline stand building operation may be interrupted when equipment is being used in the online drilling operations. Therefore, a more efficient method and system for handling tubulars that minimizes or eliminates human physical contact with the tubulars and lifting equipment, restricts and

controls the path of the tubulars throughout the entire offline operation, requires minimal inefficient movement of the tubulars, and eliminates any potential interruption of the tubular building and drilling process would be desirable.

BRIEF SUMMARY OF THE INVENTION

[0018] A system and method for building and handling oilfield tubular stands is disclosed that utilizes a single derrick, drilling deck, and rotary system, and separates the drilling process from the offline stand building process. A guided path horizontal to vertical arm ("HTV") lifts tubulars stored horizontally on the catwalk, and then moves the tubulars in a single vertical plane such that no interference occurs with the drilling process, and multiple articulated motions are reduced. The HTV moves the tubulars between the catwalk and the preparation hole for assembling or disassembling the tubular stands. A stand arm is positioned for lifting and lowering the tubulars into and out of the preparation hole, and transporting the tubulars vertically for storage into an auxiliary tubular racking station in the upper part of the derrick.

[0019] A bridge racker crane also mounted in the upper part of the derrick removes tubular stands from the auxiliary tubular racking station and transports them to either the top drive, or to another tubular racking station in the derrick. Using the auxiliary tubular racking station, the offline stand building operation is advantageously uninterrupted when the bridge racker crane is unavailable due to its need to participate in the simultaneously occurring drilling operations.

BRIEF DESCRIPTION OF THE DRAWINGS

[0020] A better understanding of the present invention can be obtained with the following detailed descriptions of the various disclosed embodiments in the drawings:

[0021] **FIG. 1** is an elevational view of the present invention on an exemplary embodiment of a drilling rig.

[0022] **FIG. 2** is a section plan view taken along line 2-2 of FIG. 1 showing the catwalk, the primary tubular advancing station, the primary tubular handling station, and the auxiliary tubular handling station.

[0023] **FIG. 2A** is a plan view showing the stand arm, the preparation hole, and the auxiliary tubular racking station in alternative locations relative to each other as compared with FIG. 2 and the other drawings.

[0024] **FIG. 3** is a section plan view taken along line 3-3 of FIG. 1 showing the bridge racker crane, the auxiliary tubular racking station, and the first and second tubular racking stations.

[0025] **FIG. 4** is a section elevational view taken along line 4-4 of FIG. 1 showing the bridge racker crane, the first and second tubular racking stations, and in phantom view the bridge racker crane in different positions with and without the casing frame.

[0026] **FIG. 5** is a section elevational view taken along line 5-5 of FIG. 1 showing the V-door of the drilling rig and the guided path horizontal to vertical arm ("HTV").

[0027] **FIG. 6** is an enlarged elevational view of the HTV with a tubular shown in the horizontal position in solid line and in the vertical position in phantom view.

[0028] **FIG. 7** is an elevational view of the HTV, rotated 90° about the vertical axis from Fig. 6, with the tubular in the horizontal position.

[0029] **FIG. 8** is an enlarged detailed elevational view of the bridge racker crane of the present invention.

[0030] **FIG. 9** is a detailed elevational view of an attachment for the bridge racker crane to handle casing sections or stands.

[0031] **FIG. 10** is an elevational view of the preparation hole shown in broken view with portions of the pulley cable shown in phantom view.

[0032] **FIG. 11** is an elevational view of the preparation hole, rotated 90° about the vertical axis from FIG. 10.

[0033] **FIG. 12** is an enlarged detailed view of the preparation hole of the present invention as shown in FIG. 11.

[0034] **FIG. 13** is a section view of the preparation hole taken along line 13-13 of FIG. 10.

[0035] **FIG. 14** is a section view of the preparation hole taken along line 14-14 of FIG. 10.

[0036] **FIG. 15** is a section view of the preparation hole taken along line 15-15 of FIG. 10.

[0037] **FIG. 16** is an elevation view taken along line 16-16 of FIG. 2, illustrating the HTV lowered for gripping a tubular in the first horizontal position.

[0038] **FIG. 17** is a view similar to FIG. 16 with the HTV and the tubular in the raised second horizontal position.

[0039] **FIG. 18** is a view similar to FIG. 16 with the HTV guiding the tubular to a vertical position aligned with the preparation hole, as shown in FIGS. 10 and 11, and additionally illustrating the deck crane delivering a casing section to the online carriage for advancement to the well center.

[0040] **FIG. 19** is a view similar to FIG. 16 with the HTV lowering the tubular into the preparation hole while the casing section is simultaneously positioned on the online carriage.

[0041] **FIG. 20** is a view similar to FIG. 16 with the HTV raised, and the stand arm lifting the drill pipe section up and out of alignment with the preparation hole while the casing section, moved by the online carriage towards well center, is simultaneously being gripped by the top drive.

[0042] **FIG. 21** is a view similar to FIG. 16 with the HTV gripping a second drill pipe section while the casing section is simultaneously being lowered by the online top drive above the well center.

[0043] **FIG. 22** is a view similar to FIG. 16 with the second drill pipe section guided into alignment with the preparation hole while the casing section is lowered by the online top drive into the well center.

[0044] **FIG. 23** is a view similar to FIG. 16 with the second drill pipe section lowered into the preparation hole and being connected with the first drill pipe section with a tubular make up device while the casing section is simultaneously lowered into the well center.

[0045] **FIG. 24** is a view similar to FIG. 16 illustrating the HTV with a third drill pipe section in the raised second horizontal position before being guided into alignment with the

preparation hole, the connected first and second drill pipe sections shown being lifted by the stand arm out of alignment with the preparation hole to allow the third tubular to be received into the preparation hole.

[0046] **FIG. 25** is a view similar to FIG. 16 with the first and second tubulars being connected with the third tubular by the tubular make up device.

[0047] **FIG. 26** is a view similar to FIG. 16 with the stand arm lifting the stand of three tubulars from the preparation hole to the auxiliary tubular racking station.

[0048] **FIG. 27** is a view similar to FIG. 16 with the bridge racker crane, as shown in FIGS. 3, 4 and 8, gripping the stand of tubulars from the auxiliary tubular racking station and moving the stand to a drill pipe racking station.

[0049] **FIG. 28** is a view similar to FIG. 16 showing the HTV with a casing section in the second horizontal position while the bridge racker crane, with the casing attachment of FIG. 9, is simultaneously positioning a stand of casing in the auxiliary tubular racking station.

[0050] **FIG. 29** is a view similar to FIG. 16 showing a casing section raised from the well center by the top drive and laid down onto the carriage, and the laydown trolley on the top of the carriage being driven in the direction of the arrow to tilt the casing section.

[0051] **FIGS. 30A, 30B AND 30C** illustrate the circuitry for the simultaneous pipe handling system of the present invention.

DETAILED DESCRIPTION OF THE INVENTION

[0052] The present invention involves a system and method for offline building of tubular stands, while drilling operations are simultaneously and independently occurring. As shown in the drawings, this offline stand building comprises moving tubulars from a horizontal position on the catwalk **22** adjacent to the V-door **26** of the derrick **10**, lifting and guiding the tubulars in the same plane to a vertical position directly above a preparation hole **46** with a horizontal to vertical arm **48**, lowering the vertically positioned tubulars into the preparation hole **46**, using a stand arm **58** to move the tubulars in the vertical position for connection into a stand by an auxiliary tubular make up device **56**, and transporting the stand vertically to an auxiliary tubular racking station **60** in the upper part of the derrick **10**. A bridge racker crane **86** transports the tubular stands from the auxiliary tubular racking station **60** to either the top drive **12**, or to first **128** or second **130** tubular racking stations.

[0053] An exemplary drilling rig, generally indicated as **R**, of the invention is shown in FIG. 1. Although an offshore cantilever jack-up rig **R** is shown, other drilling rig or structure configurations and embodiments are contemplated for use with the invention both for

offshore and land drilling. For example, the invention is equally applicable to drilling rigs such as semi submersibles, submersibles, drill ships, barge rigs, platform rigs, and land rigs. Also, although the following is described in terms of oilfield drilling, the disclosed embodiments can also be used in other operating environments for non-petroleum fluids. Further, although the use of a top drive or power swivel is preferred, the invention can also be used with other rotary systems, including, but not limited to, a rotary table.

[0054] Reviewing both FIGS. 1 and 2, a drilling structure or derrick **10** extends above the drilling deck **16**. A top drive **12** or power swivel is preferably used to rotate the drill string and bit in the borehole. The top drive **12** is suspended from the traveling block in the conventional manner. A drilling hoist or drawworks is mounted in the derrick **10**, as is known by those of ordinary skill in the art. The top drive **12** is aligned vertically with the well center **14** in the drilling deck **16**. A deck revolving crane **18** is mounted on the rig **R** for use in lifting and moving tubulars **20**.

[0055] Catwalk

[0056] In FIG. 2, the catwalk **22** is supported on the top of the catwalk truss structure **24** (see FIGS . 5 and 17) adjacent to the drilling deck **16**. As best shown in FIG. 5, the catwalk **22** is in the same plane as the drilling deck **16**, and is adjacent the V-door **26** of the derrick

10. Although a single V-door 26 is shown, it should be understood that derricks may contain more than one V-door, and that the tubulars transported or moved in the present invention may be staged through different V-doors. Turning back to FIG. 2, the online or primary side of the catwalk contains the primary tubular handling station 28, which includes a carriage 30 whose longitudinal axis or centerline is substantially in alignment with the well center 14. A mechanically driven pusher trolley 38 on the carriage 30 is provided to move tubular 36 to and from the well center 14. Although a single catwalk 22 and catwalk truss structure 24 is shown, it should be understood that two different catwalks and supporting structures could be employed to support the primary tubular handling station 28 and the auxiliary tubular handling station, generally indicated at 54, as will be described below. Further, it should be understood that the two different catwalks could be set at different orientations and/or elevations. Although the base 25 (FIG. 17) of the column supporting the catwalk truss structure 24 is shown as fixed, it should be understood that rollers are contemplated at the base so that the catwalk truss structure 24 could be rolled with the drilling deck 16 and derrick 10 if they were also configured to move between well locations.

[0057] A primary tubular advancing station 13 comprises at least the well center 14. Also, a drilling hoist, the top drive 12, a tubular make up device 42, and other equipment necessary

to advance tubulars into the well center **14** can be provided in the primary tubular handling station **13**. A mousehole **32** is located radially outward from the well center **14**, and is positioned substantially on a line between well center **14** and the longitudinal centerline of the carriage **30**. The carriage has wheels that run on two parallel rails **34** mounted on the top of the catwalk **22**. The rails **34** extend across the drilling deck **16** to a location near the well center **14**.

[0058] As shown in FIG. 2, a single tubular **36** can be placed on the top of the carriage **30**. The carriage **30** transports the tubular **36** along the rails **34** from the primary tubular handling station **28** to the mousehole **32** or well center **14**. A pusher trolley **38**, whose wheels run on two parallel rails mounted on top of the carriage **30**, pushes the tubular **36** toward the well center **14** or mousehole **32**. A hydraulic lifter **39** (shown in elevation in FIG. 20) is located at the end of the carriage **30** nearest the well center **14**. A section of the top surface of the carriage **30** is hinged so that the hydraulic lifter **39** can raise the unhinged end to elevate the end of the tubular **36** nearest well center **14**. The top drive **12** or other similar equipment can then engage the tubular **36** for lifting. When tubular **36** is removed from the well center **14**, the pusher trolley **38** can be replaced with a laydown trolley **40** (shown in storage in FIG. 2; and shown in use in FIG. 29) to receive the lower end of the vertical tubular when the

carriage **30** is moved near the well center **14**. A remotely operable tubular make up device **42** (also known to those skilled in the art as an iron roughneck) is positioned near the well center **14** and the mousehole **32** for use in assembling and disassembling tubular stands.

[0059] HTV

[0060] As further shown in FIG. 2, the offline or auxiliary side of the catwalk **22** has a pipe rack **43** for the horizontal staging of tubulars. As discussed below, pipe rack **43** is fabricated for the placement of one tubular **44** substantially in alignment with a preparation hole **46**. As will be discussed below in detail, the tubular **44** is preferably in alignment with the preparation hole **46** to facilitate the guided path movement of the tubular by the horizontal to vertical arm **48** (referred to as HTV). The pipe rack **43** preferably stores approximately 5 auxiliary tubulars. Any type of tubular can be placed in the area for pick up by the HTV **48**. As best shown in elevation view in FIG. 5, the pipe rack **43** has a hydraulically operated indexing arm assembly **50** that rolls the tubulars toward the pick up location for the HTV **48**. Hydraulically activated separators **52** isolate the one tubular **44** that is to be gripped by the HTV **48**. The pipe rack **43** is also indexed or marked so that the operator of the deck crane **18** can place the tubulars in a consistent location. The deck crane **18** is used to place tubulars on both sides of the catwalk **22** (see FIG. 18). Tubulars on the carriage **30** and on the pipe

rack **43** are both in the horizontal position, are parallel to each other, and have access to the V-door **26** of the derrick **10**.

[0061] An auxiliary tubular handling station, generally indicated as **54**, is shown in FIG. 2. The auxiliary tubular handling station **54** comprises at least a stand arm or pick up arm **58**. Also, the HTV **48** and the preparation hole **46** and an auxiliary tubular make up device **56** (e.g. iron roughneck) can be provided in and/or adjacent to the auxiliary tubular handling station **54**. FIG. 2A illustrates the capability of the stand arm **58** to grip tubulars in either, when lowered, the preparation hole **46** on the drilling deck **16** (shown in phantom view), or, when raised, in the auxiliary tubular racking station **60** mounted up in the derrick. FIG. 2A shows an alternative configuration to that shown in FIG. 2 and the other drawings of the location of the stand arm **58** in relation to the auxiliary tubular racking **60**. FIGS. 5 and 7 show the auxiliary tubular handling device or HTV **48** as seen from the catwalk **22**. FIG. 6 best shows the HTV **48** gripper assembly **62** having grippers **62A** or **62B** that grips a tubular **44** as shown in FIGS. 6 and 7. The HTV **48** has a single arm. The HTV **48** moves vertically and perpendicular with the drilling deck **16** using a hoist **65** (see FIG. 16) driven trolley assembly **64** that is mounted to two rails **66** attached to a substantially vertical frame **68** connected to the derrick **10**. The hoist can also be mounted on the drilling deck **16**. It is

contemplated that a rack and pinion or a hydraulic cylinders mechanism could be used in lieu of a hoist driven system. The HTV **48** is fabricated so that it can grip a substantially horizontal tubular from the pipe rack **43** on the offline side of the catwalk **22**, lift the tubular vertically from the catwalk **22** while keeping the tubular substantially horizontal to a second horizontal position (shown in FIG. 17), and thereafter guide the tubular in the same plane 90° so that the tubular **72** is in vertical alignment with the preparation hole **46** (shown in FIG. 18). The size, shape, and configuration of the HTV is exemplary and illustrative only, and other sizes, shapes, and configurations can be used to create the same guided movement of the tubular.

[0062] Preparation Hole

[0063] The preparation hole **46** is shown in detail in FIGS. 10 to 15. The depth of the preparation hole **46** can be adjusted for the different lengths of tubulars placed in it. The variable length is necessary to accommodate, for example, drill pipe (27 to 32 feet), and casing (37 to 43 feet). The depth of the preparation hole **46** can be adjusted so that there is enough of the tubular extending above the drilling deck **16** to allow the auxiliary tubular make up device **56** to grip the tubular in the hole **46** and connect or disconnect it with another tubular above the hole **46**. The HTV **48** can also set the lower end of a tubular in the

preparation hole **46**, and the tubular can be independently advanced into the hole, as shown in FIGS. 10 to 15, after it is released by the HTV. The preparation hole **46** can hold smaller tubulars, such as completion tubing (for example 2 7/8 inch OD), and larger tubulars, such as casing (for example 9 5/8 inch OD). Since different diameter tubulars will be placed in the preparation hole **46**, it is contemplated that the preparation hole **46** could include a centralizer to center the tubular so that the vertical centerline of the tubular remains in vertical alignment with the vertical centerline of the preparation hole **46**. The centralizer could comprise an inflatable member or hydraulically radially inwardly driven members to center the tubular.

[0064] Stand Arm

[0065] Returning to FIGS. 2 and 2A, the stand arm **58** can pick up a single tubular **20** or stands of two or more tubulars. Preferably the stand arm **58** has a gripper head **74** attached to the end of a telescoping arm **76**. The gripper head **74** allows tubulars to be rotated while within its grip, as the tubulars are threaded. The pick up point for a tubular is slightly below the "upset" location on the tubular where the outside diameter (OD) of the tubular changes diameter. As best shown in FIG. 20, the stand arm **58** is mounted to a hoist **78** driven trolley assembly **80** (see plan view in FIG. 2A) that moves vertically and perpendicular with the drilling deck **16**. The trolley assembly travels on two vertical rails **82** that are attached to a

substantially vertical frame **84** mounted to the derrick **10**. Although the hoist is shown on top of the vertical frame **84**, it should be understood that the hoist could also be mounted on the drilling deck 16. Although a hoist driven system is shown, it should also be understood that a rack and pinion or hydraulic cylinders drive system could be used instead. As shown in FIG. 2, the stand arm **58** could move in a horizontal plane along the longitudinal axis of the trolley assembly **80**, which is parallel to the line between the tubular **44** and the preparation hole **46**. A telescoping arm **76** (see FIG. 2A) could be used to allow the stand arm **58** to extend and retract in a horizontal plane perpendicular to the line between the tubular **44** and the preparation hole **46**. While the stand arm **58**, as shown in FIG. 2, does not rotate about a vertical axis, the alternate embodiment stand arm **58**, as shown in FIG. 2A, can pivot about pivot pin **58A** in a horizontal plane about a vertical axis. In either embodiment, when the stand arm is in its lowest position near the drilling deck **16**, the telescoping arm **76** can extend out to grip with the head **74** tubulars extending out of the preparation hole **46**. The stand arm **58** is fabricated to lift a tubular or stand out of the preparation hole **46**, and thereafter retract and either move or rotate so as to hold the tubular or stand in a substantially vertical position in the area of the auxiliary tubular handling station **54** but out of the path of a tubular moved by the HTV to the preparation hole **46**. The stand arm **58** is also fabricated to reverse the

steps for controlled movement of a tubular or stand from the auxiliary tubular racking station **60** to the preparation hole **46** for disconnection by the auxiliary tubular make up device **56**. The stand arm **58** length and load carrying ability is adjustable for any combination of different sized tubulars. The stand arm **58** is further capable of controlled movement of a tubular stand in a vertical position up the derrick **10**, and placing it in the auxiliary tubular racking station **60**.

[0066] Bridge Racker Crane

[0067] As shown in FIGS. 3 and 4, a bridge racker crane **86** is mounted in the upper part of the derrick **10**. Two parallel horizontal support beams **88** for the bridge crane **86** are attached in the upper part of the derrick to the derrick uprights **90**. Each support beam **88** is preferably positioned an equal distance from the well center **14**, so that the center of the bridge crane **86** can be moved in vertical alignment with the well center **14**. Rails **92** are mounted to the top of each of the support beams **88**. The crane bridge beam **94** spans horizontal and perpendicular between the two support beams **88**. The crane bridge beam carriage assemblies **96** (see FIGS. 4 and 8) have wheels **98** attached to and resting on their respective rails **92**. As illustrated in FIG. 4, at least one end carriage assembly has a rack and pinion drive unit **100** to move the bridge beam **94** along the rails **92**. A cross travel unit **102**,

as shown in FIG. 4 and in section view in FIG. 8, is mounted on the bridge beam **94**. The cross travel unit **102** has wheels **104** that that run on the bridge beam **94**, and a rack and pinion drive unit **106** to move the cross travel unit **102** along the length of the bridge beam **94**. A slewing ring **108** under the cross travel unit **102** connects with a mast and cylinder guard truss **110** mounted under the cross travel unit **102**. The slewing ring **108** allows the truss **110** to rotate about a vertical axis, as best shown in FIG. 4. As shown in FIG. 8, a grip head assembly **112** is mounted to the truss **110** by a trolley assembly **114**. The wheels **116** of the trolley assembly **114** run on vertical rails **118** mounted on the truss **110**. The trolley assembly **114** is raised and lowered with a system of pulleys **120**. Although a system of pulleys **120** is shown, it should be understood that other systems are contemplated, such as rack and pinion and hydraulic cylinders.

[0068] Due to the difference in length between casing and drill pipe, casing stands typically consist of two tubulars, whereas drill pipe stands typically consist of three tubulars. As shown in FIG. 9, when casing is being handled, a casing frame **122** can be attached to the trolley assembly **114** mounted on the truss **110**. The casing frame **122** is attached to the trolley assembly **114** at the storage hanger points **124** of the casing frame **122**. The casing

frame 122 has a casing grip head 126 that can be used to grip casing in the vertical position at the location of the upset or collar.

[0069] Tubular Racking Stations

[0070] As shown in FIGS. 3 and 4, three tubular racking stations are mounted in the upper derrick 10 for storage of tubular stands. The first tubular or casing racking station 128 (shown in elevation in FIG. 4) is set at a lower elevation than the second tubular or drill pipe racking station 130. It is anticipated that the shorter tubular stands, such as casing, will be placed in the first tubular racking station 128, whereas longer stands, such as drill pipe, will be placed in the second tubular racking station 130. Both first and second tubular racking stations (128, 130) are conventional finger boards as understood by those skilled in the art. Remotely operable spears or lances 129 are used to hold the tubulars into position while in storage. When the derrick arrangement precludes the spears or lances 129 extending beyond the envelope or footprint of the derrick 10, conventional fingers, such as used on the first 128 or second 130 tubular racking stations, are contemplated. The auxiliary racking station 60 is mounted below the first tubular racking station 128. The bridge racker crane 86 is able to travel over the area of all three racking stations, as well as the well center 14. It can maneuver tubulars into and out of all three tubular racking stations. The bridge crane can

also move tubulars between any of the three tubular racking stations and the top drive **12**. A derrick man's control station cab **132** (as shown in FIG. 4) is mounted in the upper derrick **10** for control of the bridge crane **86**, the auxiliary tubular racking station **60**, and the first **128** and second **130** tubular racking stations. The block control diagram for the derrick man's control station cab **132** is shown in FIG. 30A. A drill floor control station cab **134** is mounted on the derrick **10** above the drilling deck **16** (as shown in FIG. 5) for control of the HTV **48**, stand arm **58**, preparation hole **46**, and carriage **30**. The block control diagram for the drill floor control station cab **134** is shown in FIG. 30B. FIG. 30C shows the connection of both control stations with the centralized power unit **140**.

[0071] Method of Use

[0072] Offline

[0073] The present invention is also directed to a method of offline stand building while drilling operations are simultaneously and independently occurring. It should be understood that while the offline stand building operation occurs as described below, drilling operations may be simultaneously occurring. For example, while offline stand building is occurring, the bridge racker crane **86** can remove completed tubular stands from any of these three tubular racking stations **60**, **128** or **130** and carry them to the top drive **12** for drilling or placement in

the well center **14**. Alternatively, single horizontal tubulars, such as tubular **36**, can be advanced from the carriage **30** directly to a location near the well center **14**. The top drive **12** can attach to the end of a single tubular **20** (FIG. 20), lift it into the vertical position (FIG. 21), and move it through or stab it into the tubular extending above the well center **14**. The top drive **12** can be engaged for drilling, and the process repeated when another tubular is needed.

[0074] It should also be understood that while the method of building stands of three tubulars is described below, the same method can be used for the construction of stands with other numbers of tubulars. With that understanding, according to one exemplary embodiment of the method of the invention, an offline tubular stand may be assembled in the following manner:

[0075] As shown in FIG. 16, the HTV **48** grips a single tubular **44** (referred to as the first tubular) on the pipe rack **43** on the offline side of the catwalk **22** while in the first horizontal position. The first tubular **44** is lifted straight up perpendicular to the catwalk **22** to the second horizontal position, as is shown in FIG. 17. The tubular is then rotated 90° in the same plane so that it is in vertical alignment with the preparation hole **46** (FIGS. 6 (phantom view) and 18). As shown in FIG. 19, the HTV **48** then lowers the vertical tubular **44** straight

down into the preparation hole **46**, where the tubular **44** is released by the HTV **48**. The preparation hole **46** is adjusted so that when the tubular **44** is released, a portion of the tubular **44** remains above the drilling deck **16**. The HTV **48** moves straight up vertically, and simultaneously rotates back 90° to the second horizontal position (FIG. 20). While the above actions of the HTV **48** are simultaneously occurring, the stand arm **58**, which is at its lowest vertical position near the drilling deck **16** (FIG. 2A phantom view), extends to the preparation hole **46** and grips the first tubular **44**. As shown in FIG. 20, the stand arm **58** lifts the tubular **44** out of the preparation hole **46** while maintaining the tubular in the vertical position. The stand arm **58** thereafter retracts and moves and/or rotates so as to move the vertical tubular out of vertical alignment with the preparation hole **46** in the area of the auxiliary tubular handling station **58** so as not to interfere with the path of the HTV **48**.

[0076] As shown in FIG. 21, the HTV **48** lowers to the first horizontal position, where it grips another single tubular **70** (referred to as the second tubular) that has been rolled into position with the indexing arm assembly **50** on the pipe rack **43** on the offline side of the catwalk **22** (FIG. 5). The HTV **48** then moves straight up to the second horizontal position, similar to the position of FIG. 20 and again rotates 90° in the same plane aligning the second tubular so that it is vertically over the preparation hole **46** (FIG 22). The HTV **48** lowers the

second tubular **70** into the preparation hole **46**, and releases it. The HTV **48** then simultaneously moves straight up and rotates 90° back to the second horizontal position. As is shown in FIG. 23, simultaneously while that occurs, the stand arm **58** extends and moves or rotates back so as to vertically align the first tubular **44** over the preparation hole **46**. The stand arm **58** then lowers the first tubular **44** so that the auxiliary tubular make up device **56** can connect it with the second tubular **70** (FIG. 23). The stand arm **58** then lifts the tubular stand (**44**, **70**) out of the preparation hole **46**, and again retracts and moves or rotates to move the vertical stand (**44**, **70**) out of alignment of the HTV **48** with the preparation hole **46**. As shown in FIG. 24, while the stand arm **58** is performing such operations, the HTV **48** simultaneously picks up, lifts, and rotates a third tubular **72** in the same manner as previously described. The HTV **48** lowers the third tubular **72** into the preparation hole **46**, and releases it. Again, a portion of the third tubular **72** remains extended out of the preparation hole **46** above the drilling deck **16**. The stand arm **58** moves the tubular stand (**44**, **70**) back into alignment with the preparation hole **46**, and lowers the stand (**44**, **70**) over the third tubular **72** for connection by the auxiliary tubular make up device **56** (FIG. 25).

[0077] As shown in FIG. 26, the stand arm **58** lifts the completed stand (**44**, **70**, **72**) out of the preparation hole **46** and moves it in a vertical position to the auxiliary racking station **60**

for placement and release. The stand arm **58** can extend and move or rotate as necessary to maneuver tubulars between the preparation hole **46** (FIG. 2A phantom view) and the auxiliary racking station **60** (FIG. 2A solid lines). While the auxiliary racking station **60** preferably has capacity for approximately 10 tubular stands, other capacities are contemplated.

[0078] As shown in FIG. 27, the bridge crane **86** can remove a tubular stand (shown for illustrative purposes as a drill pipe stand (**44**, **70**, **72**) although any other stand in the station **60** could have been used) from the auxiliary racking station **60** when not performing online operations. The bridge crane **86** can move a stand to either the first **128** or second **130** tubular racking stations as appropriate and necessary, or it can move a stand directly to the top drive **12**. The same operation is shown in FIG. 28 with a tubular stand (**44A**, **70A**) of casing. The casing frame **122** is attached to the bridge crane **86** for handling casing stands that have been placed in the first tubular racking station **128**. The remotely operable lances **129** are shown in end view in the first tubular racking station **128**.

[0079] As can now be seen from the above, as the bridge crane **86** is being used for online operations, then the offline stand building activities can still continue uninterrupted. The bridge crane **86** is not in the critical path of the offline stand building operation. There will

be occasions when the bridge crane **86** will work with either the offline or online operations, and not hinder the speed and functionality of the other operation.

[0080] Online

[0081] While FIGS. 16 to 28 were described above relative to the offline operations, FIGS. 18 to 22 also illustrate how the primary or online drilling operations can proceed simultaneously with these offline operations. As shown in FIG. 18, the deck crane **18** places a tubular **20** on the carriage **30** while the offline operation is occurring. As shown in FIGS. 19 to 20, the carriage **30** moves the tubular **20** across the drilling deck **16** and toward the well center **14**. The hydraulically activated front pipe lifter **39** slightly elevates the end of the tubular **20** near the well center **14**, where the tubular is gripped by the top drive **12** (FIG. 20). The top drive **12** then lifts the tubular **20** to the vertical position (FIG. 21) in alignment with the well center **14**, and thereafter lowers the tubular **20** (FIG. 22). The above steps can be performed again with a second tubular so that the second tubular is positioned for connection by the tubular make up device **42** with the tubular extending above the well center.

[0082] Laydown

[0083] The online and offline operations can also be simultaneously and independently performed in reverse order from that described above for removal, disconnection, and

laydown of tubulars. In the primary or online operation, the top drive **12** pulls the tubular string up through the well center **14** for the disconnection of either a single tubular or a tubular stand from the string using the tubular make up device **42**. If a tubular stand is disconnected, it can then be lifted up the derrick **10** for transfer to the bridge crane **86**, and transported to one of the tubular racking stations. The stands of tubulars can be simultaneously and independently disconnected and moved to the pipe rack **43** on the offline side of the catwalk **22** using the stand arm **58** and the HTV **48**. If a single tubular, for example tubular **20** (FIG. 29), is disconnected, it can then be maneuvered with the top drive **12** so that the lower end of the vertical tubular **20** is placed on the laydown trolley **40** positioned at the end of the carriage **30**, which carriage has been positioned near the well center **14**. The carriage is then moved away from the well center **14** and back toward the catwalk **22** as shown in FIG. 29.

[0084] The foregoing disclosure and description of the invention is illustrative and explanatory thereof, and various changes in the details of the illustrated system and construction and the method of operation may be made without departing from the spirit of the invention.

CLAIMS:

1. A system for drilling, said system comprising:

a drilling deck;

a drilling structure disposed with said drilling deck;

a primary tubular advancing station having a well center and disposed with said drilling structure for advancing a first tubular to said well center;

an auxiliary tubular handling station for handling a second tubular;

said drilling deck having a preparation hole positioned with said auxiliary tubular handling station for receiving the second tubular;

an auxiliary tubular handling device for positioning the second tubular in a substantially vertical position above said preparation hole;

an auxiliary tubular racking station elevated above said auxiliary tubular handling station for holding the second tubular from said auxiliary tubular handling station, wherein the second tubular is received in said preparation hole, positioned in a substantially vertical position above said preparation hole or held in said auxiliary tubular racking station while the first tubular is independently and simultaneously advanced through said primary tubular advancing station to said well center; and

a bridge racker crane configured to move the second tubular between said auxiliary tubular racking station and said well center;

wherein said auxiliary tubular handling device is configured to directly position the second tubular with said auxiliary tubular racking station; and

wherein said auxiliary tubular handling device operates independently of said bridge racker crane.

2. The system of claim 1 wherein said system further comprises:

a primary tubular racking station positioned above said primary tubular advancing station for receiving at least one tubular from said auxiliary tubular racking station.

3. The system of claims 1 or 2, wherein said auxiliary tubular handling device comprises:

a stand arm for moving the second tubular between said preparation hole and said auxiliary tubular racking station.

4. The system of claims 2 or 3, wherein said bridge racker crane is configured to move the second tubular between said primary tubular racking station and said auxiliary tubular racking station.

5. The system of any one of claims 2-4, wherein said bridge racker crane is configured to move the second tubular between said well center and said primary tubular racking station.

6. The system of any one of claims 3-5, wherein said auxiliary tubular handling device is configured to assemble a plurality of tubulars so that the first of the plurality of tubulars moved to the preparation hole is on top of the assembled tubulars.

7. A system for drilling, said system comprising:

a drilling deck;

a drilling structure disposed with said drilling deck;

a primary tubular advancing station having a well center and disposed with said drilling structure for advancing a first tubular to said well center;

an auxiliary tubular handling station for handling a second tubular;

an auxiliary tubular handling device for positioning the second tubular in a substantially vertical position;

a first tubular racking station elevated above said auxiliary tubular handling station for holding the second tubular from said auxiliary tubular handling station, wherein the second tubular is positioned in a substantially vertical position above said drilling deck and held in said first tubular racking station while the first tubular is advanced through said primary tubular advancing station to said well center; and

a bridge racker crane is configured to move the second tubular between said first tubular racking station and said well center;

wherein said auxiliary tubular handling device is configured to directly position the second tubular with said first tubular racking station; and

wherein said auxiliary tubular handling device operates independently of said bridge racker crane.

8. The system of claim 7, further comprising a second tubular racking station positioned above said drilling deck for holding the second tubular, wherein said bridge racker crane is configured to move the second tubular between said second tubular racking station and said well center.

9. The system of claim 7, wherein said auxiliary tubular handling station comprises a stand arm, and the system further comprises a guided path horizontal to vertical arm positioned adjacent to said stand arm to guide the second tubular from a substantially horizontal position to a substantially vertical position adjacent to said stand arm, wherein said stand arm and said guided path arm are configured to operate during the primary tubular advancing station

advancing the first tubular to said well center and independently of said primary tubular advancing station.

10. The system of claim 9, wherein said stand arm operates independently of said bridge racker crane.

11. The system of claims 8 or 9, wherein the first tubular does not interfere with said stand arm.

12. The system of claims 8 or 9, wherein the first tubular does not interfere with said stand arm and said guided path horizontal to vertical arm.

13. The system of any one of claim 9-12, wherein said stand arm operates independently of said bridge racker crane.