What is claimed is:

1. A ~~tent comprising~~
~~a~~ tent structure comprising:
   a. two or more arched lattice frames each supported at an elevated position ~~above a ground~~ by at least one upright truss;
   b. a plurality of straight frames mounted between two adjacent arched lattice frames; ~~and~~
   c. at least one tracker system mounted onto a top of ~~the~~ said arched lattice frames, wherein the tracker system has a tracker slot throughout a length of the arched frame;
   ~~wherein a setup and dismantling of the tent structure is always performed at lower level at which the arched frames are upright on the ground;~~
   d. at least one roof canvas installed over the tent structure, wherein an edge ~~sides~~ of the roof canvas ~~along the length~~ is inserted ~~from one side of the tracker system~~ into ~~the~~ a tracker slot~~s of adjacent arched frames~~ and then reeled in from the opposite ~~other~~ side of the tent structure ~~to cover a top of the tent structure~~; and
   e. a plurality of rods connecting a center top straight frame and at least one straight frame adjacent to the center top straight frame~~,~~ to support a center of the roof canvas laid over the tent structure,

wherein each arched lattice frame is connected to a lifting and lowering system that includes a chain block or automated pulley system to lift the tent structure upright after installing the roof canvas.

2. The tent structure of claim 1, ~~is configured during~~ wherein setup ~~to~~ is comprised of the steps of:
   a. initially positioning the two or more arched lattice frames upright on the ground;
   b. mounting the straight frames between the adjacent arched frames to form the tent structure;
   c. laying the roof canvas over the tent structure;

d. lifting the tent structure with the roof canvas above the ground ~~at~~ to an elevated position; and
e. supporting each arched frame in the tent structure using the upright truss.

~~3. The tent of claim 2 is further configured during setup to connect each arched frame to a lifting and lowering system to lift the tent structure.~~

~~4. The tent of claims 1 to 3, wherein the upright truss supports the tent structure at elevated position by connecting one end of the upright truss with the arched frame and other end resting on the ground.~~

~~5. The tent of claims 1 to 4, wherein the tent structure with the roof canvas is lifted up by at least:~~

~~lifting one side of all the arched frame in the tent structure and then lifting all the arched frame at other side of the tent structure; or~~

~~lifting all the arched frames at both the sides in synchronization~~.

3. ~~6.~~ The tent structure of claim 1 or 2 ~~5,~~ ~~is configured during~~ wherein take-down and dismantling ~~to~~ is comprised of the steps of:
a. removing ~~remove~~ the roof canvas from over the tent structure;
b. connecting each arched frame to the lifting and lowering system to lower the tent structure;
c. removing ~~remove~~ the upright truss at each end of the arched frame;
d. lowering ~~lower~~ the tent structure from the elevated position to the ground;
e. dismantling ~~dismantle~~ the straight frames between the two arched frames; and
f. dismantling ~~dismantle~~ two or more arched frames.

~~7. The tent of claim 6 further comprising comprises the step of connecting each arched frame to the lifting and lowering system to lower the tent structure~~.

~~8. The tent of claim 6 further comprises removing the roof canvas after lowering the tent structure~~.

~~9. The tent of claims 1 to 8, wherein the tent structure is lowered~~ by ~~at least~~:

~~lowering one side of all the arched frames in the tent structure and then lowering all the arched frames at other side of the tent structure; or~~

~~lowering all the arched frames at both the sides in synchronization.~~

~~10. The tent of claims 3 to 9, wherein the lifting and lowering system is a chain block or automated pulley system.~~

4. ~~11.~~ The tent structure of claim ~~3~~ 2 or ~~9~~ 3, wherein the lifting and lowering system is a hydraulic system.

5. ~~12.~~ A method for setting up a tent structure comprising the steps of:

a. placing two or more arched lattice frames upright ~~on a ground~~, wherein each arched lattice frame has at least one tracker system with a tracker slot mounted on a top of the arched lattice frame;
b. mounting a plurality of straight frames between two adjacent arched frames to form a tent structure;
c. connecting a center top straight frame and its adjacent straight frame before laying at least one roof canvas, using a plurality of rods to support the roof canvas laid over the tent structure;
d. laying the roof canvas over the tent structure between two adjacent frames of the tent structure;
e. lifting the tent structure ~~at~~ to an elevated position by connecting ~~tracker system of~~ each arched frame to a lifting and lowering system; and
f. supporting the tent structure using an upright truss,

wherein the tent structure is assembled at ground level and then raised up using the lifting and lowering system.

6. ~~13.~~ The method of claim 5, ~~12~~ further comprising ~~comprises~~ the step of inserting the sides of the roof canvas ~~along a length from one side of the tracker system~~ into the tracker slots ~~of adjacent arched frames~~ and then reeling in from the ~~other~~ opposite side ~~of the tent structure~~ to cover ~~a top of~~ the tent structure.

7. ~~14.~~ The method of claim 5, ~~12~~ further comprising the step of assembling the upright truss and the straight frames at the ends of the arched frame at or near ground level ~~a safer reachable height in the elevated tent structure using a climbing device of a safer height~~.

8. ~~15.~~ The method of claim 5 ~~12~~ further comprising the steps of:

temporarily ~~temporary~~ supporting the arched frames using at least one support rod to facilitate installation of the tent structure at ~~the~~ ground level;

tightening the arched frames and the straight frames together with at least one fastener; and

removing the support rod before lifting.

9. ~~16.~~ The method of claim 5 ~~12~~, wherein the tent structure with the roof canvas is lifted up by ~~at least~~:

lifting one side of ~~all~~ the arched frame in the tent structure ~~and then~~ followed by lifting ~~all~~ the arched frames at ~~other~~ opposite side of the tent structure; or

lifting ~~all~~ the arched frames at both the sides in synchronization.

~~17. The method of claim 12, wherein the roof canvas is laid over the straight frame by at least:~~

~~laying on each space between the adjacent arched frames one by one; or~~

~~laying on all the spaces between the adjacent arched frames together.~~

~~18. The method of claim 12, wherein the entire tent structure is assembled at the ground level and then elevated above the ground using the lifting and lowering system.~~

10. ~~19.~~ The method of any one of claims ~~12~~ 5 to ~~18~~ 9, wherein the lifting and lowering system is a chain block or automated pulley system.

11. ~~20.~~ The method of any one of claims ~~12~~ 5 to ~~18~~ 9, wherein the lifting and lowering system is a hydraulic system.

12. ~~21~~. A method for take-down and dismantling a tent structure comprising:

a. removing one or more roof canvas from over a tent structure, ~~wherein the tent structure comprises one or more arched frames, a plurality of straight frames between the arched frames and at least one tracker system with a tracker slot mounted on a top of the arched frame~~;
b. removing one or more upright truss mounted at ends of the arched frames in the tent structure at an elevated position;
c. lowering the tent structure from ~~the~~ an elevated position by connecting each arched frame to a lifting and lowering system;
d. dismantling a plurality of rods between a center top straight frame and at least one adjacent straight frame of the lowered tent structure ~~using climbing device of a safer height~~;
e. dismantling the straight frames between two adjacent arched frames from the tent structure; and
f. dismantling the arched frames,

wherein the tent structure is lowered to the ground using the lifting and lowering system that includes a chain block or automated pulley system and then dismantled at the ground level.

13. ~~22.~~ The method of claim ~~21~~ 12 further comprising the step of dismantling the upright truss and the straight frames at the ends of the arched frame at or near ground level ~~a safer reachable height in the elevated tent structure using the climbing device of the safer height~~.

~~23. The method of claim 21 further comprises comprising removing the roof canvas along the length from the tracker slots of adjacent arched frames by reeling out from the other side of the tent structure to uncover the top of the tent structure.~~

14. ~~24.~~ The method of claim ~~21~~ 12, wherein the tent structure is lowered by ~~at least~~:

lowering one side of all the arched frames in the tent structure and then lowering ~~all~~ the arched frames at ~~other~~ the opposite side of the tent structure; or

lowering all the arched frames at both the sides in synchronization.

~~25. The method of claim 21, wherein the canvas is removed from the straight frame by at least:~~

~~removing from each space between the adjacent arched frames one by one; or~~

~~removing from all the spaces between the adjacent arched frames in synchronization.~~

~~26. The method of claim 21, wherein the tent structure is lowered from the elevated level to the ground using the lifting and lowering system and then dismantled at the ground level.~~

~~27. The method of claims 21 to 26, wherein the lifting and lowering system is a chain block or automated pulley system.~~

15. ~~28.~~ The tent of any one of claims ~~21 to 26~~ 12 to 14, wherein the lifting and lowering system is a hydraulic system.