CLAIMS

1. An offshore work facility comprising:

a jack-up drilling rig comprising three or more legs and a main hull portion in which the legs are arranged, and a cantilever and a drilling equipment are removed,

an additional structure added to the main hull portion, and

a crane mounted on the additional structure.

2. The offshore work facility according to claim 1, wherein-the main hull portion is configured as a floating body structure in which an internal space is formed, and

the internal space is divided into a plurality of sections by a bulkhead.

3. The offshore work facility according to claim 2 wherein the additional structure is supported by the main hull portion using the bulkhead.

4. The offshore work facility according to claims 1, wherein the main hull portion has a multi-layer structure.