ABSTRACT

[Problem] To provide a unit room and floor panel that are easy to transport and for which level adjustment can be performed easily after being installed in the installation site, a method for transporting the unit room and floor panel, and a method for installing the unit room and floor panel.

[Solution] A framework 40 is mounted above a unit room 20 so that guide pieces 44 are positioned along the outer surfaces of the four corners of the unit room 20. Hooks 47 provided at the lower ends of linear bodies 46 are hooked into eyebolts 8. An upper part of the linear bodies 46 is hooked by a hook 50 of a crane and the unit room 20 is lifted and transported. After the unit room is carried above a floor slab 60, the unit room is placed on the floor slab 60. After the hooks are removed from the eyebolts 8, the level adjustment of the unit room 20 is performed by turning the eyebolts 8 so as to project downward.