

ABSTRACT

REMOVAL METHOD FOR EMBEDDED STRUCTURE

Provided is a method that can remove an embedded structure along with appropriately injecting a sealing material.

The method is a method of removing an embedded structure and comprises: installing an injection tube at a position apart from the embedded structure by a certain distance or more, attaching a string-like member to the embedded structure, and hoisting the string-like member thereby pulling up the pile, as well as injecting a sealing material from the injection tube into the ground in a flow amount determined corresponding to at least a diameter of the embedded structure.

[Figure 1]