WELLHEAD ASSEMBLY WITH TELESCOPING CASING HANGER

BACKGROUND OF THE INVENTION

1. Field of the Invention

[0001] The present invention relates in general to subsea wellhead assemblies, and in particular to a wellhead housing, wherein an actuator mechanism causes the load on a casing hanger in the wellhead housing to be transferred to the housing even in the event the casing hanger may be set in a high position in the wellhead housing.

2. Description of the Prior Art

[0002] In a typical subsea well, wellhead housing is positioned on the floor of a body of water at the upper end of the well. The wellhead housing is a tubular member having a bore aligned with the well bore. A string of large diameter casing attaches to the lower end of the wellhead housing and extends into the well bore. After further drilling into the earth through the wellhead housing, a smaller diameter string of casing is installed. A casing hanger at the upper end of the smaller diameter string of casing is landed in the bore on a load shoulder in the wellhead housing.

[0003] Debris and cuttings from the well are a continuing concern in subsea wellhead equipment design and operation. The debris and cuttings can become lodged or located between the casing hanger and other load bearing structure in the wellhead, such as another casing hanger in a stack in the wellhead housing or the wellhead housing itself. Thus, there were concerns with proper seating of casing hangers for load transfer or sharing purposes. The problem became worse when several hangers were stacked on top of each other, as was typical in subsea wellheads.

[0004] For the uppermost, stacked hangers, the use of shim sets with adjustable shims was contemplated. Adjustments were to be made after appropriate measurements were made in the wellhead housing at the wellhead to determine the required amount of adjustment. However, a separate trip of equipment from the surface to the wellhead was required which was time consuming and thus expensive. There was also concern expressed about the ability to make accurate measurements to determine the required adjustment.

SUMMARY OF THE INVENTION

[0005] Briefly, the present invention provides a new and improved wellhead assembly, having wellhead housing with a bore and an installed casing hanger in the bore. The wellhead housing has a support shoulder adjacent the bore and a telescoping casing hanger for securing to a string of casing and lowering into the wellhead housing. A split, resilient load ring is carried in a retracted initial position on the casing hanger. The load ring is movable outwardly to a set position in engagement with the wellhead housing. An actuator is mounted with the casing hanger below the load ring for moving the load ring from the initial position to the set position. The actuator includes a resilient mechanism for adjusting for height variations between the position of the load ring and the support shoulder during movement of the load ring to the set position to land the telescoping casing hanger in the wellhead housing.

[0006] The present invention further provides a new and improved method for installing a telescoping casing hanger atop an installed casing hanger in a bore of wellhead housing at the upper end of a well in a body of water. A support shoulder is provided in the bore of the wellhead housing. A split, resilient load ring is mounted in a recessed initial position in the telescoping casing hanger. An actuator is mounted on the telescoping hanger below the load ring, and then a string of casing is secured to the telescoping casing hanger and the telescoping

casing hanger lowered into the wellhead housing. The telescoping hanger is landed on the installed casing hanger. The load ring is activated with the actuator and moved to expand and land on the support shoulder of the wellhead housing, and the casing hanger lands on the load ring. The position of the load ring on the support shoulder is adjusted to compensate for differences in the landed height of the telescoping hanger and the installed casing hanger.

BRIEF DESCRIPTION OF THE DRAWINGS

[0007] Figure 1 is a vertical sectional view of a portion of a wellhead housing having a telescoping casing hanger according to the present invention located in a landed position.

[0008] Figure 2 is an enlarged view of a portion of the structure circled and identified by reference numeral 2 in Figure 1.

[0009] Figure 3 is an enlarged view taken partly in vertical section of the portion of the telescoping casing hanger of Figure 1.

[00010] Figure 4 is an enlarged view of a portion of the structure circled and identified by reference numeral 4 in Figure 3.

[00011] Figure 5A, 5B, 5C and 5D are vertical sectional views of the structure of Figure 4 during an activation sequence of landing the telescoping casing hanger of the present invention in normal landed position.

[00012] Figures 6A, 6B, 6C and 6D are vertical sectional views of the structure of Figure 4 during an activation sequence of landing the telescoping casing hanger of the present invention in a higher than normal landed position.

[00013] Figures 7A and 7B are vertical sectional views of the structure of Figure 4 during a sequence of confirming proper landing of the telescoping casing hanger of the present invention.

[00014] Figures 7C and 7D are vertical sectional views of the structure of Figure 4 during a deactivation sequence of retrieving or pulling the telescoping casing hanger of the present invention.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

[00015] In the drawings, a telescoping casing hanger H according to the present invention is shown (Figure 1) landed on a previously installed hanger such as a bridging hanger B in a wellhead housing 10. The wellhead housing 10 is of the conventional type installed as a component of a subsea wellhead assembly located at the sea floor. The telescoping casing hanger H includes an activation ring 12 which is mounted extending circumferentially below a collar or shoulder 14 of the body 16 of the telescoping casing hanger H. The activation ring 12 takes the form of an upper activation ring sleeve member 18 (Figure 4), a lower activation ring sleeve member 20 and a compressible spring 22. A wave spring is suitable form of spring for the spring 22, although others might be used.

[00016] A load ring 24 is mounted on an upper surface 26 of the upper activation ring member 18 extending circumferentially about the casing hanger body 16 between the shoulder 14 and the activation ring 12. The load ring 24 is a split, resilient ring and adapted to transfer load from the casing hanger H to the wellhead housing. The load ring 24 has a tapered upper inner surface 28 adapted for engagement with and relative sliding movement with respect to a corresponding tapered circumferentially extending lower surface 30 of the casing hanger body 16.

[00017] As will be set forth, the load ring 24 is moved inwardly and outwardly with respect to a load transfer landing shoulder 32 formed in an annular groove or bore 34 extending about the interior of the wellhead housing 10 to land the casing hanger H in the wellhead housing 10. Such movement takes place during the landing and extraction or pulling of the casing hanger H in the wellhead housing 10.

[00018] The activation ring 12 also includes an outer collar 36 mounted on an outer surface 38 of the lower activation ring member 20. A set of circumferentially disposed pins 40 are mounted with the collar 36 extending downwardly for engagement an upper portion 42 of a previously installed casing hanger, such as bridging hanger B, in the wellhead housing 10.

[00019] The telescoping casing hanger H includes a lock ring 44 with circumferentially extending outwardly inclined surfaces. The lock ring 44 is mounted for movement within a circumferential slot 46 formed between correspondingly inclined surfaces formed extending circumferentially about the casing hanger body 16 adjacent the upper activation ring member 18.

[00020] When the casing hanger H is being lowered or tripped into the well bore, the lock ring 44 prevents the activation ring 12 from moving if prematurely contacted. This in turn prevents the load ring 24 from early movement. In this way, the casing hanger H is not damaged during movement in the well bore as a result of premature operation of activation ring 12 caused by contact with obstructions which might be encountered in the well bore.

[00021] A snap ring 50 is mounted in a corresponding slot 52 extending circumferentially about a lower outer portion of the activation ring member 18. The snap ring 50 is fitted into the slot 52 and extends outwardly to engage a lip formed in an inner side of the lower activation ring member 20. The snap ring 50 in the preloaded position shown in Figure 4 captures the spring 22 and maintains the spring 22 in a preloaded state so that a large axial force is required to telescopically collapse the activation ring 12.

[00022] The activation ring 12 also includes one or more circumferentially extending ratchet lip or rim members 54 on its upper inner surface adjacent the casing housing body 16. The ratchet member structure 54 extends downwardly and is adapted to engage an overpull check

ring 56. The overpull check ring 56 includes an outwardly extending lip 58 extending about the casing hanger body 16 above the upper activation ring member 18. Overpull check ring 56 is mounted in a circumferentially extending recess or groove formed in the casing housing body member 16.

[00023] The overpull check ring 56 due to this location engages and locks the activation ring 12 only when the load ring 24 has fully expanded (Figures 5C and 5D). This allows an operator to make an overpull once the casing hanger has landed. As will be set forth, the overpull check ring 56 thus permits verification or confirmation that the telescoping casing hanger 16 is properly landed in the wellhead housing 10 and the load transferring mechanisms have properly functioned.

[00024] In the operation of the present invention, an activation sequence in situations when the casing H is landed at its intended normal height position on the previously installed hanger B in the wellhead housing is illustrated in Figures 5A through 5D. The casing hanger H and associated casing suspended beneath it is lowered through a riser downwardly into the wellhead housing 10. The pins 40 come into contact with the structure of the previously installed hanger. The pins 40 are pressed upwardly into the body of the casing hanger H (Figure 5A) forcing the lock ring 44 to retract (Figure 5A) and unlock the activation ring 12. Further displacement of the casing hanger H downwardly (Figure 5B) occurs as a result of slacking off casing weight. This brings the now unlocked and movable activation ring 12 into contact (Figure 5C) with the top surface of the hanger B already installed below the casing hanger H.

[00025] Further weight downwardly on the casing hanger H collapses the wave spring 22 of the casing hanger H and causes outward expansion of the load ring 24 until contact is made with

the bore 34 of the wellhead housing 10, thus limiting further outward expansion. The load ring 24 is now fully set (Figure 5D) and the casing hanger H is in position for load transfer purposes. The preload on the spring 22 captured by the activation ring 12 is at a force level greater than the maximum expansion load on the load ring 24 to permit this to occur.

[00026] Figures 6A through 6D illustrate an activation sequence in the event that the hanger B below the casing hanger H is sitting at a higher than normal position due the presence of cuttings or other debris. By comparison of Figures 6A through 6D with Figures 5A through 5D it can be seen that the load ring 24 in Figures 6A and 6B is at a higher position with respect to the bore 34 of the wellhead housing 10 than in Figures 5A and 5B. The pins 40 come into contact and are pressed upwardly into the body of the casing hanger H (Figure 6A). Activation of pins collapses internal lock ring (7B)

[00027] Activation ring expands load ring until it contacts housing wall (7C). The activation ring 12 expands the load ring 24 until it contacts the inner wall of the wellhead housing 10 (Figure 6C), at a higher position than illustrated in Figure 5C.

[00028] Further weight applied downwardly by slacking casing weight on the casing hanger in the position illustrated in Figure 6C collapses the wave spring 22 and load ring 24 is now fully set (Figure 6D). It can be seen that the casing hanger H in Figure 6D is also now at the fully landed normal height position shown in Figure 5D.

[00029] The sequence of events described above occurs sequentially and seamlessly and requires only the slacking off of casing weight in order to take place. As has been set forth the presence of the overpull check ring 56 which is engaged with the activation ring 12 (Figure 7A)

allows the operator to confirm (Figure 7B) that proper landing has occurred by making an overpull on the installed assembly.

[00030] In order to deactivate and remove the casing hanger H when it is landed either position, with the load ring 24 fully set (Figure 7A), the casing hanger H is lifted until top of load ring 24 contacts wellhead housing in the position shown in Figure 7B. Further lifting tension or force shears the engagement (Figure 7C) between the overpull check ring 56 and the ratchet structure 54 on the activation ring 12, allowing the load ring 24 to collapse to a position where the load ring 24 is fully collapsed (Figure 7D) and it is now possible to pull the casing hanger H out of wellhead housing 10.

[00031] The present invention has significant advantages. It provides an improved rate of success due to the capability to accommodate variations in installed height of casing hangers due to cuttings, debris or otherwise. The present invention provides an assembly that is much less sensitive to the presence of cuttings or debris. This permits the well operator more time for drilling operations rather than circulation and hole conditioning operations.

[00032] While the invention has been shown in only one of its forms, it should be apparent to those skilled in the art that it is not so limited but is susceptible to various changes without departing form the scope of the invention.

CLAIMS

Claims:

1. A wellhead assembly, comprising:

a wellhead housing (10) having a bore (34) therein and an installed casing hanger (B) mounted therewith, the wellhead housing (10) having a support shoulder (32) adjacent the bore (34);

a telescoping casing hanger (H) for securing to a string of casing and lowering into the wellhead housing (10);

a split, resilient load ring (24) carried in an retracted initial position on the casing hanger (H), the load ring (24) being movable outwardly to a set position in engagement with the wellhead housing (10);

an actuator mounted with the casing hanger (H) above the load ring (24) for moving the load ring (24) from the initial position to the set position;

the actuator including a resilient mechanism for adjusting for height variations between the position of the load ring (24) and the support shoulder (32) during movement of the load ring (24) to the set position to land the telescoping casing hanger (H) in the wellhead housing (10).

2. The wellhead assembly according to claim 1, wherein the actuator (12) comprises:

an actuator ring (12), the actuator ring (12) moving with respect to the casing hanger (B) when the telescoping casing hanger (H) lands on the installed casing hanger (B).

3. The wellhead assembly according to claim 2, wherein the actuator ring (12) comprises:

an upper activation ring sleeve member (18);

a lower activation ring sleeve member (20);

the upper and lower activation ring sleeve members (18, 20) being movable with respect to each other when the telescoping hanger (H) lands on the installed casing hanger (B).

4. The wellhead assembly according to claim 3, wherein the resilient mechanism comprises a spring (22) mounted between the upper and lower activation ring sleeve members (18, 20) of the actuator ring (12).

5. The wellhead assembly according to claim 1, further including:

a lock ring (44) mounted on the telescoping hanger and restraining the actuator from movement until unlocked.

6. The wellhead assembly according to claim 5, wherein the lock ring (44) is collapsible to unlock under applied force.

7. The wellhead assembly according to claim 1, further including:

an overpull check ring (56) mounted between the actuator and the telescoping hanger (H) to allow initial upward test force to be applied on the telescoping hanger (H) to confirm proper landing.

8. The wellhead assembly according to claim 7, wherein the overpull check ring (56) shears in response to an increased upward force larger than the initial upward test force to allow retraction of the load ring (24).

9. A telescoping casing hanger (H) for securing to a string of casing and lowering into the wellhead housing (10) to land on a casing hanger (B) in a wellhead housing (10), comprising:

a split, resilient load ring (24) carried in an retracted initial position on the casing hanger (H), the load ring (24) being movable outwardly to a set position in engagement with the wellhead housing (10);

an actuator mounted with the casing hanger (H) above the load ring (24) for moving the load ring (24) from the initial position to the set position;

the actuator including a resilient mechanism for adjusting for height variations between the position of the load ring (24) and the support shoulder (32) during movement of the load ring (24) to the set position to land the telescoping casing hanger (H) in the wellhead housing (10).

10. The telescoping casing hanger (H) according to claim 9, wherein the actuator comprises:

an actuator ring (12), the actuator ring (12) moving with respect to the casing hanger (H) when the telescoping casing hanger (H) lands on the installed casing hanger (B).

11. The telescoping casing hanger (H) according to claim 10, wherein the actuator ring (12) comprises:

an upper activation ring sleeve member (18);

a lower activation ring sleeve member (20);

the upper and lower activation ring sleeve members (18, 20) being movable with respect to each other when the telescoping hanger (H) lands on the installed casing hanger (B).

12. The telescoping casing hanger (H) according to claim 11, wherein the resilient mechanism comprises a spring (22) mounted between the upper and lower activation ring sleeve

members (18, 20) of the actuator ring (12).

13. The telescoping casing hanger (H) according to claim 9, further including:

a lock ring (44) mounted on the telescoping hanger (H) and restraining the actuator from movement until unlocked.

14. The telescoping casing hanger (H) according to claim 13, wherein the lock ring (44) is collapsible to unlock under applied force.

15. The telescoping casing hanger (H) according to claim 9, further including:

an overpull check ring (56) mounted between the actuator and the telescoping hanger (H) to allow initial upward test force to be applied on the telescoping hanger (H) to confirm proper landing.

16. The telescoping casing hanger (H) according to claim 15 wherein the overpull check ring (56) shears in response to an increased upward force larger than the initial upward test force to allow retraction of the load ring (24).

17. A method for installing a telescoping casing hanger (H) atop an installed casing hanger (B) in a bore (34) of wellhead housing (10) at the upper end of a well in a body of water, comprising:

(a) providing a support shoulder (32) in the bore (34) of the wellhead housing (10);

(b) mounting a split, resilient load ring (24) in a recessed initial position in the telescoping casing hanger (H);

(c) mounting an actuator on the telescoping hanger (H) below the load ring (24); then

(d) securing a string of casing to the telescoping casing hanger (H) and lowering the

telescoping casing hanger (H) into the wellhead housing (10);

(e) landing the telescoping hanger (H) on the installed casing hanger (B);

(f) activating the load ring (24) with the actuator and moving the load ring (24) to expand and land on the support shoulder (32) of the wellhead housing (10) and the casing hanger (B) to land on the load ring (24); and

(g) adjusting the position of the load ring (24) on the support shoulder (32) to compensate for differences in the landed height of the telescoping hanger (H) and the installed casing hanger (B).

18. The method according to claim 17, further including the step of:

confirming landing of the telescoping hanger (H) with the wellhead housing (10).

19. The method according to claim 17, further including the step of:

moving the load ring (24) inwardly from engagement with the wellhead housing (10).

20. The method of claim 19, further including the step of:

extracting the telescoping hanger (H) from the wellhead housing (10).