

ABSTRACT

In main modules 100A to 100T, a height of a ceiling panel 111 in a vertical direction is changeable in a ceiling module 110 and a height of a space between the ceiling panel 111 and a floor panel 121 is flexibly changed in a floor module 120 with the floor panel 121. An under-floor module 130 is moved along a floor surface by a moving device 400 and the main modules 100A to 100T are connected to other main modules 100A to 100T and keep airtightness of a space between the ceiling panel 111 and the floor panel 121.

Figure 1